



MIDWEST
RELIABILITY
ORGANIZATION

PROTECTION SYSTEM COMMISSIONING WEBINAR

MRO PROTECTIVE RELAY SUBGROUP

July 14, 2022

10:00 a.m. – 11:30 a.m. Central

CLARITY

ASSURANCE

RESULTS



MIDWEST
RELIABILITY
ORGANIZATION

Max Desruisseaux

**Senior Power Systems Engineer
Reliability Analysis
Midwest Reliability Organization**


CLARITY

ASSURANCE

RESULTS

WebEx Chat Feature

Open the Chat Feature:



The chat feature will appear to the right of the WebEx window.

Attendees should chat their questions to: “MRO Host”.

Select MRO Host by using the drop down arrow in the “To” field.

Purpose

- **Misoperations Due to Errors Occurring During Commissioning is a Medium Risk in the MRO reliability risk matrix.**
- **Provide information on and raise awareness of the Joint Review of Protection System Commissioning Programs report.**
- **Highlight some of the work being done by entities and the PRS.**
- **Discuss Performance Data**

Discussion Topics

- **Overview of Protection System Commissioning Report**
- **Best Practices**
- **Case Studies**
- **PRS Misoperations Phase II Report**
- **Event Analysis Data**
- **MIDAS Data**



MIDWEST
RELIABILITY
ORGANIZATION

Gilbert Lowe III, P.E.

**Electrical Engineer
Office of Electric Reliability
Federal Energy Regulatory Commission**

CLARITY

ASSURANCE

RESULTS



Protection System Commissioning Program Review Project



FERC
FEDERAL ENERGY REGULATORY COMMISSION



Efforts to Reduce ^{CU}Misops From Inadequate PSC

- 2015-2021 NERC Issued Lessons Learned
- 2017 IEEE WG I-25 guide Commissioning Testing of Protection Systems
- 2019 Analysis of MIDAS finding 18-36% of Misops could have been prevented better PSC



FERC
FEDERAL ENERGY REGULATORY COMMISSION



PSC Review Project Process

- Eight registered entities and one PSC contractor.
- Selected based on geographical locations and performance data such as events and Misop rates.
- Surveys and Interviews on participants' PSC programs and Procedures.
- Used the IEEE WG I-25 guide as a benchmark.
- Team discussed and agreed upon the best practices, opportunities for improvement, and related recommendations.



FERC
FEDERAL ENERGY REGULATORY COMMISSION



PSC Programs Key Elements

- Stated goals and objectives
- Well-defined plans to perform commissioning
- Clearly identified lines of responsibility
- Authority given to responsible parties
- Feedback methods for improvements



FERC
FEDERAL ENERGY REGULATORY COMMISSION



PSC Program^{CUI} Recommendations

- All entities should document a formal PSC program. Having a formal, documented program in a central location (e.g., a single document) allows easy reference to all 5 elements of the PSC program.
- Have well-documented training requirements of classroom and on-the-job training coupled with some type of proficiency assessment to ensure well-qualified commission testing personnel.
- Entities should use internal controls to find, track and correct issues in their PSC programs. Entities should implement controls to ensure that lessons learned are documented and fed back into future project design and commissioning processes.
- Entities should separate the commissioning agent from the design and installation processes.



FERC

FEDERAL ENERGY REGULATORY COMMISSION

NERC
NORTH AMERICAN ELECTRIC
RELIABILITY CORPORATION

PSC Program Best Practices

- Designated senior management from different departments to share responsibility for program approval. Senior management involvement is likely to draw attention to and support commission testing programs.
- Multi-layer contractor selection process that vetted the contractor's firm then its employees assigned to project followed by frequent meetings with the contractor to review work performance
- Intranet access to lessons learned in standardized form that is reviewed during scoping of new projects and shared with industry groups



PSC Procedure Core Elements

- Planning and sequencing
- Print and technical review
- Preparing installed equipment for modification
- Equipment and device acceptance testing
- Equipment isolation
- Functional testing
- Operational (or in-service load) checks
- Documentation



FERC
FEDERAL ENERGY REGULATORY COMMISSION



PSC Procedure Recommendation

- Ensure PSC team (including contractors) performs independent design review prior to the start of construction
- Maintain a documented isolation log in a standardized format that includes the repositioning of test switches, temporary jumpers, and shorting blocks; who made the changes; time and date of the change; and when the equipment was returned to normal.
- CT circuit errors represent a significant portion of misops primarily due to incorrect CT ratios, polarity, and left in shorted position.
- All Entities should perform current testing on all phases to ground, phase-to-phase, and 3-phase faults. This will ensure that CT ratios, CT and polarity, and polarization of ground elements is correct for all fault scenarios.



FERC

FEDERAL ENERGY REGULATORY COMMISSION



PSC Procedure Best Practices

- PSC procedures included back-to-back testing on tie lines, unfamiliar relay models, configurations, and/or firmware editions.
- Engineering package identified all equipment that needed isolated or shorted ensuring adequate in-service protection
- Peer review process to assess test results and avoid possible bias.
- Maintain an isolation log and tagged the circuits at the point of isolation for equipment isolation.





MIDWEST
RELIABILITY
ORGANIZATION

Sarah Marshall

Team Lead
System Protection
Alliant Energy

CLARITY

ASSURANCE

RESULTS



Alliant Energy's Commissioning Best Practices

How to Keep Bugs Out of the Ointment

Sarah Marshall – Team Lead System Protection, Alliant Energy



Pillars for Success



STANDARDS



COMMISSIONING
CHECKLISTS



HUMAN PERFORMANCE
TOOLS

System Protection Standards Committee



All template changes reviewed quarterly for approval.



Review team: engineers, operations, management.



Limits the frequency of major design changes to 1-2 times per year.


Hardware changes
New protection schemes
Operational changes impacting the design



Minor changes are permitted as needed at any time.

Firmware version changes
Correcting design errors

Substation Drawing Template



Relay Settings Template

Relay Setpoints File

Global

Group 1

Set 1

General Settings

Line Settings and Fault Locator

Phase Overcurrent Elements

Neutral Ground Overcurrent Elements

Residual Ground Overcurrent Elements

Negative-Sequence Overcurrent Elements

Phase Time-Overcurrent Elements

Neutral Ground Time-Overcurrent Element

Residual Ground Time-Overcurrent Elements

Negative-Sequence Time-Overcurrent Element

Breaker Failure

Second Harmonic Blocking

Load Encroachment Element

Directional Elements

Voltage Elements

Synchronism Check Elements

Frequency Elements

Rate-of-Change-of-Frequency Elements

Redosing Relay

Switch-onto-Fault Logic

Communications Assisted Trip Schemes

Demand Elements

Other Settings

SELogic Variable Timers

Frequency Elements

Frequency Element Settings

E81 Frequency Elements

1 Select: N, 1-6

27B81P Undervoltage Block (V,sec)

84.00 ### Range = 25.00 to 300.00

Level 1

81D1P Pickup (Hz)

50.00 ### Range = 40.10 to 65.00, OFF

81D1D Time Delay (cyc)

6.00 Range = 2.00 to 16000.00

Level 2

Errors: Found 41 Setting(s)

Group	Setting	Value	Message
Group 1	27B81P	84.00 ###	Error: Group 1 27B81P Setting value "84.00 ###" must be greater than or equal to 25.00 and less than or equal to 300.00.
Group 1	50G2P	4.000 ###	Error: Group 1 50G2P Setting Value "4.000 ###" is not a valid value for this setting.
Group 1	50P1P	34.60 ###	Error: Group 1 50P1P Setting Value "34.60 ###" is not a valid value for this setting.
Group 1	50P2P	5.00 ###	Error: Group 1 50P2P Setting Value "5.00 ###" is not a valid value for this setting.

System Protection
Relay Settings Documentation

Distribution Feeder
Guideline – 351-BBxx

Section: SP-GUID-210
Version: 6.00
Issued: 02/04/2022

Note: 51Q asserts if negative-sequence current $3I_2 = I_A + a^2 I_B + a I_C$ for $a = 1\angle 120^\circ$, is greater than negative-sequence time-overcurrent element pickup setting 51QP. Note that this formula is valid only for ABC counterclockwise rotating three-phase system.

Directional Element

E32 = N Directional elements are not used.
ELOP = N Note that the loss-of-potential logic still operates with ELOP = N

Voltage Element

Vnom = 120 VT nominal voltage setting in secondary volts (line-to-neutral [wye-connected VT's] or line-to line [delta-connected VT's]). See below for example calculation, at 24.9kV L-L using L-G wye connected 120:1 ratio VT's.

$$\left[\frac{24.9KV}{\sqrt{3} \times 120 : 1} \right] = 120V \quad (10)$$

Underfrequency Element

Underfrequency logic ensures that the following conditions must be met for a trip to occur:

- voltage must be present;
- close failure condition must not exist (CF=0).

Underfrequency Logic Equations

Application of underfrequency settings should be determined by the Delivery System Planners.

Underfrequency Settings:

NFREQ = 60 60 Hz nominal frequency
E81 = 1 Enable one level of frequency settings.
81D1P = (see note below) Setting should be provided by the Delivery System Planner for that area.
81D1D = 6 Cycles Underfrequency time delays are 6 cycles for all underfrequency steps.
27B81P = 84 Undervoltage block, in secondary volts (frequency elements are disabled below this voltage threshold). Set to 70% of nominal secondary L-G voltage. For example, at 24.9kV L-L using L-G wye connected 120:1 ratio VT's:

$$\left[\frac{24.9KV}{\sqrt{3} \times 120 : 1} \right] \times 70\% = 84V \quad (11)$$

Note: Under-frequency-load-shedding (UFLS) will be set by Delivery System Planning department according to MISO, if needed for your particular substation. If UFLS will be recommended to implement in the next year or two by the Delivery System Planning department we recommended setting 81D1P = 50. A setting of 50Hz is way below any UFLS setting that would be recommend by MISO, but would provide us the ability to test and verify UFLS relay logic and SCADA programming during substation commissioning without affecting system reliability and allow for an easy setpoint adjustment and re-commissioning at a later date.

Relay Settings Guide



Commissioning Template

Overview
States
Test Points
Sources
Worksheet
Inputs
Timers
Outputs
Notes
Recording
Formula References

Linear Ramp, Frequency

Test Points

Expected	Actual
50.000 Hz	

Frequency

Test Parameters

Name	Value
A Offset Frequency	51.000 Hz
B Offset Duration	20.00 cy
C ± Ramp Rate	-0.100 Hz/s
D Frequency Limit	48.000 Hz

View Graph

Action State Summary

Sources		CT/VT Ratio		Connections		Action		
Name	DC			Hi	Lo	Amplitude	Phase	Frequency
VA	☐	60	▼			120.0 V	0.0 °	Action
VB	☐	60	▼			120.0 V	-120.0 °	Action
VC	☐	60	▼			120.0 V	120.0 °	Action
IA	☐	240	▼			0.00 A	0.0 °	System
IB	☐	240	▼			0.00 A	0.0 °	System
IC	☐	240	▼			0.00 A	0.0 °	System

Control Panel

Sense Settings

Channel ID	Label	Connections	Sense Condition
S1 LN1	LN1		0->1
Sense Delay		0.00 cy	
Sense Duration		0.00 cy	
Play sound when relay operates		☐	

Jumpers

Test comments

Commissioning Checklist

Substation Commissioning Review Checklist V3	
Conduct Review 1 to 4 weeks after Checkout is Complete	
Project:	
Project Checkout Date:	
Review Completion Date:	
Review Completed With (Personnel):	
	Comment
☐ Is Corporate Project Folder Set Up Correctly (Use Template)	
☐ Commissioning Checklist	
Completed and saved to corporate project folder	
☐ Protective Relays	
As-Left settings - System Protection Engineering notified to remotely access relays and save settings to corporate database	
Protection Suite commissioning file saved to corporate project folder	
Protection Suite maintenance test plan complete	
For UFLS implemented relays confirm UF pickup and time delay were tested and Cascade has correct values entered	
☐ Instrument Transformers	
Test results saved to corporate project folder?	

Commissioning Task List

	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P
	Group	Task	Task	Task	Task	Task	Task	Task	Task	Task	Task	Task	Task	Task	Task	Task
1				As checkout date gets closer touch base with DSOV/ SCADA team to confirm checkout time/date		Ensure all pre-checkout Commissioning Checklist tasks are completed and perform 'local' checkout with DSI verification	Perform Checkout	Energize Transformer and verify LTC operation (typically completed day following checkout)	Task: Working DSOV/ SCADA Team, assigned Substation Protection Engineer and Sub Tech Support Manager/Foreman that transformer has been energized		Verify differential relaying values, relay metering and metering values in DSI are correct when sufficient load is added	Contact System Protection Engineer to have them remotely access and save the 'final' relay settings to Alliant's corporate drive	Complete field markups of as-built electrical/communications drawings, sign first page and submit to Substation Engineer	Complete Project Commissioning Checklist	Perform Project Review - Complete Substation Commissioning Review Checklist	Receive final As-Built drawings from drafting, review for accuracy against field marked up copy and replace field marked up copy in substation
2	System Tech															
3	Telecom Tech					Ensure all pre-checkout Commissioning Checklist tasks are completed and perform 'local' checkout with DSI verification	Perform Checkout						Complete field markups of as-built electrical/communications drawings, sign first page and submit to Substation Engineer	Complete Project Commissioning Checklist	Perform Project Review - Complete Substation Commissioning Review Checklist	For communications only projects - Receive final As-Built drawings from drafting, review for accuracy against field marked up copy and replace field marked up copy in substation
4	System Protection Engineering		Provide relay and SCADA programming information to technicians 2 weeks prior to System Technician	Minimum 2 weeks prior to scheduled checkout date submit SCADA information to DSOV/ SCADA Team. Build				Verify voltages and check relays and remote access to relays			Review site in DSI to ensure one line, metering, alarming, etc. are accurate	Save final relay/SCADA files to corporate drive (relay settings files, LTC Controller, 2414s, RTU, etc)				
5	DSOV/ SCADA Team (Bev & Martin)				Refer to Sub Tech Support work schedule for site checkout dates		Perform Checkout		Move site in DSI from Under Construction to Active (Monitor). Change site font color to white unless site has special consideration (2nd phase to complete, etc.). Ensure all alarm inhibits							
6	Sub Tech Support Foreman or Manager	Set date in work schedule for checkout								Send email to DSOV/ manager and supervisor, Substation Maintenance manager, DSOV/ SCADA team, System Protection Engineer and Substation Engineer notifying them that site is in service and DSOV/ has monitoring/control responsibility.					Lead Project Review - Complete Substation Commissioning Review Checklist	
7																
8																

Human Performance Tools

Pre-Job Briefing

Self-Check

3-Way
Communication

Barriers

Flagging

Equipment
Isolation List



Rely on the process.

Find a framework, then use it.





MIDWEST
RELIABILITY
ORGANIZATION

Ryan Einer, PE

**Manager
Operations Support
Oklahoma Gas And Electric Co.**

CLARITY

ASSURANCE

RESULTS

Case Studies: The Impact of Commissioning on Recent Misoperations

Ryan Einer, PE – Manager Operations Support




We Energize Life
.....


Protection System Commissioning



DCB Carrier Misoperation



DCB Carrier Misoperation






Protection System Commissioning Program

- No job is too small to establish well-defined plans to perform commissioning
- Establish a feedback method for improvements


Protection System Commissioning Process

- Functional testing of the protection system with effective component testing.
- Utilize a consistent and complete PSC test checklist that identifies specific tasks in the commissioning procedure

As Designed CT Polarity



As Built CT Polarity





Protection System Commissioning Program

- All construction projects are unique, and a one-size fits all approach to a commissioning plan will have gaps
- Clearly identified lines of responsibility

Protection System Commissioning Process

- In-service tests to verify AC voltage and current circuits to verify proper magnitude and phase relationships
- Entities should perform a final walkdown upon completion of in-service testing using a checklist to document the results
- Utilize a consistent and complete PSC test checklist that identifies specific tasks in the commissioning procedure



MIDWEST
RELIABILITY
ORGANIZATION

John Grimm, PE

Principal Systems Protection Engineer

Reliability Analysis

Midwest Reliability Organization

CLARITY

ASSURANCE

RESULTS



MIDWEST
RELIABILITY
ORGANIZATION

MRO Protective Relay Subcommittee Misoperations Phase II Report

By John Grimm, P.E. – Principal Systems Protection Engineer

CLARITY

ASSURANCE

RESULTS


PRS Whitepapers

Protection System Misoperations

<https://www.mro.net/wp-content/uploads/document-library/Protection-System-Misoperation-White-Paper.pdf>

PRS Phase II Misoperations White Paper

<https://www.mro.net/wp-content/uploads/document-library/Protective-Relay-Subcommittee-Misoperations-Phase-II-Whitepaper.docx.pdf>



Misoperations Phase II Report

- The PRS identified high impact schemes that when they misoperate or fail to operate, they can lead to more severe events.
- The areas of focus for this Phase II report are:
 - *Breaker Failure Schemes*
 - *Differential Schemes*
 - *Differential Commissioning Practices*
- The PRS reviewed the misoperation submissions for 2010 to first quarter of 2016 and identified submissions related to breaker failure and differential misoperations.

Commissioning Practices to Reduce Misoperations

- As the PRS was analyzing the misoperation submittals within the MRO, it was evident that a significant portion of the errors involved with differential misoperations could have been caught during commissioning.
- Many could have been prevented with detailed commissioning and testing practices by on-site personnel.
- The third chapter of the whitepaper addresses commissioning practices:
 - Commissioning AC circuitry
 - Commissioning DC circuitry
 - Thorough load checks during commissioning
- For effective commissioning, ***make sure that the construction schedule is not compressed to the point such that insufficient time is given to properly commission the protection schemes.***



Commissioning Practices and Checks

- **Verify orientation of components installed matches design documents.**
- **CT ratio field checks to verify the ratio in the relay settings match the CT tap settings and the CT wiring matches the drawings.**
- **Verify relay winding compensation settings are appropriate for the transformer winding being protected.**
- **Electrical test should be performed to validate CT saturation curves, CT dielectric strength, and integrity of the secondary circuits.**
- **Verify the lockout relay properly trips and blocks closing of all devices within the zone of protection.**
- **Verify CT secondary has proper grounding.**
- **Use primary current injection to verify secondary CT to relay wiring.**
- **Verify CT polarity also matches the drawings and relay settings.**
- **Other checks:**
 - Compare as-left Settings to as-received settings and report any differences to Engineering
 - Review the schematics and settings to ensure all outputs that are used are properly programmed.
 - Ensure all windings being used in differential protection are enabled.



Load Checks During Commissioning

- Load checks will help identify errors such as a mismatch between wiring and the relay settings.
- It is very important to ensure that system conditions will provide sufficient load current on the day of commissioning.
- Each of the following should be evaluated with the relay's measured values when applicable:
 - Phasor currents – Closely balanced and near 120 degree between phases
 - Power factor - Acceptable level
 - Differential current - A near zero operate current should be observed, $< I_{op}$
- All relay current inputs being used need to be load checked.



Examples of Load Checking Typical Schemes

- The whitepaper provides detailed discussion of loading checking the following typical schemes:
 - Low Impedance Bus Differential Example
 - High Impedance Bus Differential Example
 - Transformer Differential Example
 - Generator Differential Example



MIDWEST
RELIABILITY
ORGANIZATION

Rich Bauer

Associate Principal Engineer

RAPA/Event Analysis

North American Electric Reliability Corporation

CLARITY

ASSURANCE

RESULTS

NERC


NORTH AMERICAN ELECTRIC
RELIABILITY CORPORATION


MRO PRS Webinar on Protection System Commissioning


Rich Bauer
NERC RAPA/Event Analysis
July 14, 2022


RELIABILITY | ACCOUNTABILITY

































MIDWEST
RELIABILITY
ORGANIZATION

Jake Bernhagen, PE

Senior Systems Protection Engineer

Reliability Analysis

Midwest Reliability Organization

CLARITY

ASSURANCE

RESULTS



MIDWEST
RELIABILITY
ORGANIZATION

MRO Misoperations and Commissioning

By Jake Bernhagen, P.E. – Senior Systems Protection Engineer

CLARITY


ASSURANCE

RESULTS


ERO Misoperations by Year




ERO Operations by Year




MRO Misoperation Rate by Year




MRO Misoperations by Equipment Type



MRO Misoperations by Cause




MRO Human Error Misoperations



- Between 2017 & 2021, 41.6% of MRO misoperations were Human Error related (As-Left Personnel Error, Design Errors, Incorrect Settings, Logic Errors)
- 64.7% of HE are associated with transmission line misoperations
- Overall, Incorrect Settings account for
 - 24.8% of all misoperations
 - 59.7% of all HE misoperations

MRO Microprocessor Misoperations



■ As-left personnel error ■ Design errors ■ Incorrect settings ■ Logic errors

- Between 2017 & 2021, 85.2% of HE misoperations are associated with microprocessor relays
- Of those misoperations, two-thirds are associated with Incorrect Settings

MRO Performance Improvement Initiatives

- **Protective Relay Subgroup (PRS)**
- **White Papers**
- **Misoperation Peer Review Team**



MRO Protective Relay Subgroup (PRS)

The purpose of the MRO Protective Relay Subgroup (MRO PRS) is to identify, review and discuss system protection and control issues relevant to the reliability of the bulk electric system and to develop and implement regional procedures for the NERC PRC standards.

- Reports to MRO's Reliability Advisory Council (RAC)
- Consists of relay subject matter experts from companies in the MRO footprint
- Meets quarterly
- Reviews NERC Lessons Learned related to protection system components
- Periodic presentations on events that occur in MRO's region
- Periodic technical presentations by members

MRO Protective Relay Subgroup (PRS) Membership

Member	Company	Member	Company
Greg Sessler, Chair	American Transmission Company	Derek Vonada	Sunflower Electric Power Corporation
David Wheeler, Vice Chair	Southwestern Public Services Co.	Derrick Schlangen	Great River Energy
Adam Daters	ITC Holdings	Glenn Bryson	American Electric Power
Alex Bosgoed	Saskatchewan Power Corporation	Greg Hill	Nebraska Public Power District
Casey Malskeit	Omaha Public Power District	Jeff Beasley	Grand River Dam Authority
Cody Remboldt	Montana-Dakota Utilities	Josh Erdmann	Xcel Energy
David Weir	Western Area Power Administration	Matt Boersema	Western Farmers Electric
Dennis Lu	Manitoba Hydro	Ryan Einer	Oklahoma Gas & Electric



White Papers

The MRO PRS has published two white papers:

- 2016 paper covers overcurrent relaying, Direction Comparison Blocking (DCB) schemes, & Direct Transfer Trip (DTT) schemes
- 2017 paper covers breaker failure relaying, differential relay application, & commissioning practices

Misoperation Peer Review Team

Misoperations are reviewed to ensure correct and consistent reporting

- **Conducted quarterly by a subgroup of PRS members**
- **Allows participants to review a variety of misoperations and discuss solutions, findings, best practices, etc.**
- **Unusual or severe misoperations may be presented on at PRS meetings for technical discussion**

What Entities Can do to Reduce Misoperations

- Participate in and be involved with the Protective Relay Subgroup
- Company relay subject matter experts should assist in PRS relay misoperation reviews
- Reach out to the MRO PRS for misoperation assistance & advice
- Peer review relay settings and commissioning testing procedures

Protective Relay Subgroup (PRS)

- **MRO Protective Relay Subgroup**
 - <https://www.mro.net/organizational-groups/reliability-advisory-council/protective-relay-subgroup/>
- **MRO Protective Relay Subgroup Q3 Meeting, Tuesday, August 16, 2022
8:00 am - 3:00 pm CDT**
 - <https://www.mro.net/event/mro-protective-relay-subgroup-q3-meeting/>
- **MRO Protective Relay Subgroup Misoperations Phase II Whitepaper**
 - <https://www.mro.net/wp-content/uploads/document-library/Protective-Relay-Subcommittee-Misoperations-Phase-II-Whitepaper.docx.pdf>



Resources

- **Joint Review of Protection System Commissioning Programs**
 - <https://www.ferc.gov/sites/default/files/2021-11/Protection%20System%20Commissioning%20Program%20Review%20Project.pdf>
- **IEEE PSRC, WG I-25, Commissioning Testing of Protection Systems, (2017)**
 - https://www.pes-psrc.org/kb/published/reports/WG%20I-25%20Commissioning%20_Testing%20of%20Protection%20Systems%205-10-2017.pdf
- **2022 MRO Regional Risk Assessment**
 - <https://www.mro.net/wp-content/uploads/document-library/2022-MRO-RRR.pdf>



MRO PRS Protection System Commissioning Webinar



For more information, please contact:

Max Desruisseaux, Senior Power Systems Engineer

Max.Desruisseaux@mro.net

Jake Bernhagen, Senior Systems Protection Engineer

Jake.Bernhagen@mro.net

John Grimm, Principal Systems Protection Engineer

John.Grimm@mro.net

Questions